KOLAR DIVISION.

Dated 22nd July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 12 noon on 20th August 1918, for extending the A.-V. School at Bagepalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the A.-V. School at Bagepalli," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever, for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled. and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for extending the A.-V. School at Bagepalli.

Item	Per	Quantity
Earthwork excavating foundation and filling the same to basement level	C.yd.	62
Burnt stone in mud	C. ft.	2,506
Burnt brick in mud	"	3,253
Burnt stone slabs, dressed	S. ft.	291
Honnewood work wrought and put up	C. ft.	126
Roofing with first class Mangalore tiles with teak reepers, etc., complete	Sqr.	22·17
Ridge tiles set in mortar	R. ft.	104
Ventilating tiles	Each	20
Flooring with Mangalore tiles 9" sqr. over concrete bed and cement pointing over it.	Sq.	8·25
Flooring with Cuddappah slabs and cement pointing over it	"	8·45
Plastering with chunam	"	59·13
Pointing with chunam	"	5·02
Teakwood doors panelled with bolts and clamps, etc., complete	S. ft.	108
Teakwood windows inside glazed shutters and outside panelled with iron bars, hinges and clamps, etc., complete.	"	108
Teakwood ventiliator circular with glazed shutters, etc., complete	"	28
Removing and refixing Mangalore tiled roof with scantlings and wall plates	Sq.	16·32
Removing old windows and refixing the doors in the same place and old window in additional new room.	No.	2
Removing old wall to one level to admit new work over it	L. S.	
Removing and replacing old steps	No.	1
Teakwood ornamental eave boards with painting	R. ft.	261
Zinc gutters to valley with plank	No.	4
White and colour washing, two coats	S.	109·13
Chocolate painting	"	10·67
Wood oiling	"	10·00
Teak reepers, new	R. ft.	800
Chunam borders at gable ends	"	80

Dated 22nd July 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 12 noon, on 20th August 1918, for restoring Madivala Sannakere, Registered No. 102, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (200) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for restoring Madivala Sannakere, Registered No. 102, of Kolar Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

E.E.738

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Madivala Sannakere, Registered No. 102, of Kolar Taluk.

Bund	Per	Quantity
Earthwork to bund with watering and tamping, etc.	C. yd.	5,200
Earthwork breach filling with selected soil	"	2,262
Clearing silt in the breach	Lump sum	
Turfing	S. yd.	5,277
New stone work with jelly	C. yd.	1,595
Old stone work with jelly	"	245
Gravel backing to revetment	"	125
Preparing and fixing new grade stones with painting, figuring, etc.	No.	30
Index stones	"	30
B. M. stones	"	2
Register No. stone	"	1
Gauge stone	"	2
Date stone	"	1
Sluice.		
Earthwork excavation cutting open the bund and refilling	Lump sum	—
Excavation foundation	C. yd.	16
Burnt brick in surki mortar	C. ft.	763
Burnt stone slabs, dressed	S. ft.	196
Plastering with surki mortar	Sq.	4·00
Removing and refixing old gibbet and orifice stones	Lump sum	
Providing plug with rod and locking arrangements, etc., complete	"	
Waste weir left.		
Earthwork excavation	C. yd.	392
Burnt brick in surki mortar	C. ft.	1,664
Burnt stone slabs dressed	S. ft.	985
Plastering with surki mortar	Sq.	9·85
Rough stone work new	C. yd.	451
Providing stone joggles over body wall	No.	34
Waste weir right.		
Earthwork excavation	C. yd.	325
Burnt brick in surki mortar	C. ft.	1,722
Burnt stone slabs dressed	S. ft.	841
Providing stone joggles over body wall	No.	30
Plastering with surki mortar	Sq.	9·87
Rough stone work new	C. yd.	401

Dated 22nd July 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 12 noon on 20th August 1918, for restoring Suranhalli Dodkere, minor tank, Registered No. 174 of Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Suranhalli Dodkere, minor tank, Registered No. 174 of Bowringpet Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Suranahalli Dodkere tank, Registered No. 174 of Bowringpet Taluk.

Item of work	Per	Quantity
Bund—		
Earthwork to bund including watering and consolidation	C. yd.	6,752
Turfing	S. yd.	6,219
Rough stone work, new, with jelly	C. yd.	1,458
Rough stone work, old, with jelly	"	376
Providing grade with index stones including cutting figure, etc., complete	Each	25
Providing B. M. stones do do	"	2
Providing Register No. and date stone	"	1
Sluice—		
Constructing front and rear cistern	Lump	sum
Constructing masonry panel	R. ft.	28
Waste weir—		
Earthwork	C. yd.	202
Burnt brick in surki mortar	C. ft.	904
Burnt stone slabs	S. ft.	141
Plastering with surki mortar	"	8·42
Rough stone work	C. yd.	116
Providing joggles	Lump	sum

Notice dated 22nd July 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 12 noon 24th August 1918, for constructing a compound wall around the Special Lock-up at Champion Reefs, Kolar Gold Fields. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a compound wall around the Special Lock-up at Champion Reefs, Kolar Gold Fields," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for constructing a compound wall around the Special Lock-up at Champion Reefs, Kolar Gold Fields.

Item	Per	Quantity
Earthwork excavation	C. yd.	535
Concrete in chunam	C. ft.	4,035
Burnt stone in chunam	"	6,658
Burnt brick in chunam	"	19,638
Teakwood gate with masonry pillars, etc.	Lump	sum.
Plastering with chunam	S. ft.	217·3
Dismantling old wall	"	1,031
Clearing silt and removing dry stone	Lump	sum.
Coping with burnt brick in chunam and glass pieces stuck on it.	R. ft.	777
White and colour washing	Sqr.	217·3
Constructing a latrine for male and female lock-ups.		
Earthwork excavation	C. yd.	10
Burnt stone in chunam	"	183
Burnt brick in chunam	"	442
Plastering with chunam	"	7·78
Colourwashing	Sqr.	7·78
Burnt brick coping of 1½×9"	R. ft.	55
Constructing pails for seats	Lump	sum.
Tarring wall 3' high	Lump	sum.
Cuddappah slab flooring over 8" concrete and asphault pointing	Sq.	2·10
Burnt stone slabs 4" thick	S. ft.	80
V shaped concrete drain with cement plastering	R. ft.	35
Extra hydrant	Lump	sum.

V. V. KARVE,
Executive Engineer.